BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work:Improvements of Roads and Drains in Kodigehalli A K Colony and Surrounding areas in ward no 08 Kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	420.06	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means: A. Lime Concrete, cement concrete grade M-10 and below. MORTH Specification No. 202	Cum	481.24	Rupees Four Hundred Eighty One and Twenty Four Paise Only
2	64.35	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m. including cost of materials, labour, HOM complete as per specifications	Cum	287.26	Rupees Two Hundred Eighty Seven and Twenty Six Paise Only
3	21.45	Excavation in marshy soil upto 3m depth for foundations of structures as per drawing and technical specifications including removing the excavated stuff to a lead of 15m., including dewatering , shoring strutting wherever necessary watering and ramming including cost of all materials, labour, HOM complete as per specifications MORTH Chapter 12	Cum	1047.17	Rupees One Thousand Forty Seven and Seventeen Paise Only
4	36	Diversion of water course by providing Coffer dams or bunds or islands as may be necessary for piers and abutments foundations, bailing out or pumping water during excavation and until completion etc., complete. - - beyond 1.50 mtrs depth upto & including 3m depth	Cum	313.76	Rupees Three Hundred Thirteen and Seventy Six Paise Only
5	80.44	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications.	Cum	2574.74	Rupees Two Thousand Five Hundred Seventy Four and Seventy Four Paise Only
6	26.81	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement 180kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @o.57 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5408.12	Rupees Five Thousand Four Hundred Eight and Twelve Paise Only
7	178.75	Providing and removing centering, shuttering, strutting,propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per Specification.	Sqm	466.4	Rupees Four Hundred Sixty Six and Forty Paise Only
8	257.4	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications.	Sqm	379.48	Rupees Three Hundred Seventy Nine and Forty Eight Paise Only
9	139.42	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - Ready mixed Cement concrete for Beams, Staircase and Roof with M-25	Cum	5826.82	Rupees Five Thousand Eight Hundred Twenty Six and Eighty Two Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
10	13.94	Providing T.M.Tsteel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members whereever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three and Ninety Six Paise Only
11	30	Providing Weep Holes KSRRB M2200-8. Providing weep holes in Brick masonry / Plain / Reinforced concrete abutment, wing wall / return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing foce. Complete as per drawing and Technical Specifications complete as per specifications MORTH Specification No.2706 & 2200	No	155.82	Rupees One Hundred Fifty Five and Eighty Two Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

" DTS APPROVED "

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.